

Schedule of Quantity for: “Development work of football ground at A. E. C. School, Turamdih.”

N. I. T No.: TMD/MIN – 676

**[P R I C E P A R T]**

Schedule of Quantity for: Development Work of football ground at A. E. C. School, Turamdih

**NIT No. TMD/MIN –676**

<b>Item No.</b>	<b>Description of item</b>	<b>Qty</b>	<b>Unit</b>	<b>Rate Rs. P</b>	<b>Rate in words</b>	<b>Amount Rs. P</b>
<b>1</b>	Earth work in rough excavation, banking excavated earth in layers not exceeding 20 cm in depth, breaking clods watering, rolling each layer with ½ tonne roller or wooden or steel rammers, and rolling every 3rd and top-most layer with power roller of minimum 8 tonnes and dressing up in embankments for roads, floods banks, marginal banks and guide banks or filling up ground depressions, lead upto 50m and lift upto 1.5m: All kinds of soil	<b>200.00</b>	<b>CUM</b>			
<b>2</b>	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50m and lift upto 1.5m	<b>550.00</b>	<b>CUM</b>			
<b>3</b>	Disposal/carriage of Earth upto to 2.00 KM as per the direction of Engineer-in-charge.	<b>550.00</b>	<b>CUM</b>			

<b>4</b>	Supply & stacking at site dump manure from approved source, including carriage upto 1 Km (manure measured in stacks will be reduced by 8% for payment): Screened through sieve of I. S designation 4.75mm as per direction of E. I. C.	<b>200.00</b>	<b>CUM</b>			
<b>5</b>	Fine dressing of the ground as per the direction of Engineer-in-charge	<b>10000.00</b>	<b>Sqm/ 100</b>			
<b>6</b>	Uprooting weeds from the trenched area after 10 to 15 days of its flooding with water including disposal of uprooted vegetation as per the direction of Engineer-in-charge.	<b>10000.00</b>	<b>Sqm/ 100</b>			
<b>7</b>	Spreading of sludge, dump manure or/and good earth in required thickness as per the direction of Engineer-in-charge (Cost of sludge, dump manure and / or good earth to be paid separately.	<b>353.00</b>	<b>CUM</b>			
<b>8</b>	Grassing with "doob" grass in rows 5 cm apart in both directions including watering and maintenance of the lawn for 30 days or more till the grass forms a thick lawn, free from weeds and fit for mowing including supplying good earth if needed (the good earth shall be paid for separately) as per direction of Engineer-in-charge	<b>10000.00</b>	<b>Sqm/ 100</b>			

<b>8</b>	Renovating lawns including weeding, cheeling the grass, forking the ground, top dressing with sludge or manure, mixing the same with forked soil, watering and maintaining the lawn for <b>180 days</b> or more till the grass forms a thick lawn free from weeds and fit for mowing and disposal of rubbish as directed, including supplying good earth if needed but excluding the cost of sludge or manure as per the direction of Engineer-in-charge(the good earth shall be paid for separately).	<b>10000.00</b>	<b>Sqm/100</b>			
<b>10</b>	Digging holes 60cm dia and 60cm deep in ordinary soil and refilling the same with the excavated earth mixed with manure or sludge in the ratio of 2 : 1 by volume (2 parts of stacked volume of earth after reduction by 20% : 1 part of stacked volume of manure after reduction by 8%) flooding with water, dressing including removal of rubbish and surplus earth, if any, with all leads and lifts (cost of manure, sludge or extra good earth if needed to be paid for separately).	<b>200.00</b>	<b>Each</b>			
<b>11</b>	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All works upto plinth level - 1 : 3 : 6 ( 1 cement : 3 coarse sand : 6 graded stone aggregate 20mm nominal size) as per the direction of Engineer-in-charge	<b>25.00</b>	<b>CUM</b>			

<b>12</b>	Brick work with F. P. S bricks of class designation 75 in foundation and plinth in Cement mortar 1 : 6 ( 1 cement : 6 coarse sand)	<b>60.00</b>	<b>CUM</b>			
<b>13</b>	15mm cement Plaster on rough side of single or half brick wall of mix: 1 : 6 ( 1 Cement : 6 fine sand) as per the direction of Engineer-in-charge	<b>500.00</b>	<b>Sqm</b>			
<b>14</b>	Providing and fixing G. I chain link fabric fencing of required width in mesh size 25 x 25 mm made of G. I wire of dia 3mm including strengthening with 2mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-in-charge	<b>680.00</b>	<b>Sqm</b>			
<b>15</b>	Structural steel work in single section fixed with or without connecting plate including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete as per the direction of Engineer-in-charge.	<b>1000.00</b>	<b>Kg</b>			
<b>16</b>	Finishing of walls with water proofing cement paint of required shade: New work (Two or more coats applied @ 3.84 Kg/10 Sqm) as per the direction of Engineer-in-charge	<b>450.00</b>	<b>Sqm</b>			
<b>17</b>	Supply of ornamental plants not less than 16" long and watering during the plantation and complete maintenance of <b>180 Days</b> this will be reckoned from the date of completion of above work as per the direction of Engineer-in-charge	<b>200.00</b>	<b>Nos.</b>			

<b>18</b>	Painting of fencing with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work as per the direction of Engineer-in-charge.	<b>720.00</b>	<b>Sqm</b>			
<b>19</b>	Supply and stacking of good earth at site including royalty and carriage upto 1 Km (earth measured in stacks will be reduced by 20% for payment) as per the direction of Engineer-in-charge	<b>300.00</b>	<b>CUM</b>			
	Total					
	Rebate if any in words (_____)				<b>%</b>	
	Grand Total					

Grand Total in words \_\_\_\_\_

**Note:**

1. All items rates must be written in figures and words without which tenders are liable to be rejected.
2. All the pages of tender document must be duly signed by tenderer along with their seal.
3. Overall rebate, if any must be quoted in the above column only and written elsewhere shall not be considered.
4. Conditional tender submitted by the tenderer will be summarily rejected without any prejudice, hence tenderer are advice to quote their rates as per N. I. T conditions.
5. The Quoted rate should be inclusive of all taxes and duties including Service Tax

Signature with Seal