

URANIUM CORPORATION OF INDIA LIMITED

Schedule of quantities for : Miscellaneous Maintenance works of Process plant area at Turamdih

(NIT No. TMD/598 dtd 15-07-2014)

Item No.	Description of Item	Schedule qty	Unit	Rate in figure & words	Amount in Rs.
1	Fitting, fixing in positin true to line & level corrugated asbestos / translucent sheet in roofs , side cladding, gables, louvers etc. at various elevations including cutting, trimming corners, hoisting and fixing with 8mm diameter galvanized steel L or J hook bolt & seam bolt,limpet washer,bitumen washer nuts putty etc and dismantling complete as per specifications, drawings & directions of the Engineer including disposal of rubbish up to 5 KM (Only Sheets will supplied free of cost)	1500	Sq.M		
		(Rupees).			
2	Fitting, fixing Ridge and hips in A.C. Sheet roofing close fitted adjustable ridge (Only Ridge will be supplied free of cost)	200	Mtr.		
		(Rupees).			
3	Maintenance of false ceiling work including all necessary material and Labour etc.complete as per direction of Enginner -in-charge.	50	Sq.M		
		(Rupees).			
4	Repairing and maintenance of false floor pasting of PVC tiles floor complete including all necessary material and labour. as per direction of EIC.	250	Sq.M		
		(Rupees).			
5	Providing and fixing Aluminum frame work including all material and labour to complete work in all respect excluding cost of glass. Maintenance including necessary material	100	kg		
		(Rupees).			
6	Providing and fixing hinges heavy duty for door shutter including all material and labour	50	Each		
		(Rupees).			
7	Repairing and maitenance of Rolling shutter in all respect including greasing repairig replacementn of material to repairing of rolling shutter.	100	Sq.M		
		(Rupees).			

Item No.	Description of Item	Schedule Qty.	Unit	Rate	Amount
8	Miscellaneous Structural Steel work including dismantling /fabricating/installation painting steel . Steel will be supplied free of cost from our store.	1000	K.g		
9	Providing and fixing W.C. pan,all fitting including,dismantling refixing grouting and providing all necessary material and labour (Hindware make)	(Rupees).			
		4	Each		
10	Providing and fixing Urinal pan including,dismantling refixing grouting and providing all necessary material and labour (Hindware make)	(Rupees).			
		3	Each		
11	Providing and fixing wash basin including,dismantling refixing grouting and providing all necessary material and labour (Hindware make)	(Rupees).			
		2	Each		
12	Providing and fixing 30 cm wide and up to 30 cm depth AC gutter at any level and any where including dismantling refixing or replacement if required including cost of all material and labour	(Rupees).			
		100	Mtr.		
13	Providing and fixing PVC pipe 110 mmdia. pipe including dismantling refixing or replacement if required including cost of all material and labour.	(Rupees).			
		40	Mtr.		
14	Providing and fixing 5/6 mm plain / tinted Glass pan including all material such as gasket etc. to complete job as per direction of Engineer in Charge.	(Rupees).			
		50	sqm		
		(Rupees).			

Total Quoted Value Rs

Over all rebate, if any -----(in words and figures)

Note : 1) All the rates must be written in figures and words clearly without which tenders are likely to be rejected.

2) All the pages of tender document including price part must be duly signed by the tenderer along with their seal, without which tenders may likely to be rejected.

* * * * *

|

|